

**Grid Code
Modification Recommendation Form**



Title of Recommended Proposal:

MPID 307 Housekeeping Modification

Date:	15/06/2023
Recommended at GCRP Meeting No.:	The modification was presented at the Ireland GCRP Meeting dated 10 May 2023.
Grid Code Version:	12
Grid Code Section(s) Impacted by Recommended Proposal:	Definitions: <ul style="list-style-type: none">- Connection Date- Commissioning Test- Inter-jurisdictional Tie line- Simultaneous Tap Change- Spin Pump

The Reason for the Recommended Modification:

The Grid Code is a living document and while using the document several errors have come to our attention. The TSO would like to propose a fix to those errors that span various definitions within the code.

A table below outlines the definitions, the error, the red-line version of the text and the green-line version of the text.

History of Progression through GCRPs, Working Group and/or Consultation:

On the 10 May 2023 this modification proposal was presented to the EirGrid GCRP members.

Summary Note of any Objections to the Recommended Change from GCRP Members or Consultation Responses:

No objections were raised by the GCRP members.

Outcome of any GCRP Meeting Actions Relating to the Recommended Modification:

No actions were raised at the meeting.

A Table Outlining the Proposed Changes:

Definition	Error	Red Line Version Text <i>Deleted text in strike-through red font and new text highlighted in blue font</i>	Green Line Version Text
Connection Date	This definition uses an undefined term 'User's Equipment'. We have replaced that with 'User's Plant and/or Apparatus', these are defined terms.	The date on which the Commissioning Instructions have to the TSO's satisfaction been properly implemented in respect of every part of the User's Equipment User's Plant and/or Apparatus , following which the TSO shall, as soon as reasonably practicable notify the User to that effect, specifying the date of completion of such implementation.	The date on which the Commissioning Instructions have to the TSO's satisfaction been properly implemented in respect of every part of the User's Plant and/or Apparatus , following which the TSO shall, as soon as reasonably practicable notify the User to that effect, specifying the date of completion of such implementation.
Commissioning Test	This definition uses an undefined term 'User's Equipment'. We have replaced	Testing of a CDGU, Controllable PPM, Pumped Storage Plant Demand, Demand Side Units, Aggregated Generating Units, Interconnector or an item of User's Equipment User's Plant	Testing of a CDGU, Controllable PPM, Pumped Storage Plant Demand, Demand Side Units, Aggregated Generating Units, Interconnector or an item of User's Plant and/or Apparatus

	that with ‘ User’s Plant and/or Apparatus ’, these are defined terms.	and/or Apparatus required pursuant to the Connection Conditions prior to connection or re-connection in order to determine whether or not it is suitable for connection to the System and also to determine the new values of parameters to apply to it following a material alteration or modification of a CDGU, Controllable PPM, Pumped Storage Plant Demand, Demand Side Units, Aggregated Generating Units, Interconnector or of an item of User’s Equipment User’s Plant and/or Apparatus and the term “ Commissioning Testing ” shall be construed accordingly.	required pursuant to the Connection Conditions prior to connection or re-connection in order to determine whether or not it is suitable for connection to the System and also to determine the new values of parameters to apply to it following a material alteration or modification of a CDGU, Controllable PPM, Pumped Storage Plant Demand, Demand Side Units, Aggregated Generating Units, Interconnector or of an item of User’s Plant and/or Apparatus and the term “ Commissioning Testing ” shall be construed accordingly.
Inter-jurisdictional Tie Line	The first use of ‘transmission system’ in this definition is not bolded, even though it is a defined term.	The lines, facilities and equipment that connect the transmission system Transmission System of the Republic of Ireland to the transmission system of Northern Ireland.	The lines, facilities and equipment that connect the Transmission System of the Republic of Ireland to the transmission system of Northern Ireland.
Simultaneous Tap Change	The use of ‘generator’ in this definition is not bolded, even though it is a defined term.	A tap change implemented on the generator Generator step-up transformers of CDGUs , effected by Generators in response to a Dispatch Instruction from the TSO issued simultaneously to the relevant Power Stations . The Dispatch Instruction , which is normally preceded by advance warning, must be effected within 1 minute of receipt from the TSO of the Dispatch Instruction .	A tap change implemented on the Generator step-up transformers of CDGUs , effected by Generators in response to a Dispatch Instruction from the TSO issued simultaneously to the relevant Power Stations . The Dispatch Instruction , which is normally preceded by advance warning, must be effected within 1 minute of receipt from the TSO of the Dispatch Instruction .
Spin Pump	To be more specific we have included ‘Pumped Storage’ to the second reference of ‘Unit’. The term ‘Unit’ is not a defined term in isolation.	A mode of operation of a Pumped Storage Unit which is intermediate between the Pumped Storage Unit being at standstill and pumping.	A mode of operation of a Pumped Storage Unit which is intermediate between the Pumped Storage Unit being at standstill and pumping.