




# Agenda

- Moyle Interconnector Overview
- Recent Fault History
- Nature of faults
- Long term solution, considerations and timescales
- Interim work
  - Appraise interim bi-pole with metallic return option
  - Attempt to pinpoint current fault
- Summary


# ELEMENTS of the MOYLE INTERCONNECTOR



# Recent cable fault history



# Nature of Recent Faults – IRC Insulation





## Nature of Recent Faults – IRC Insulation




## Nature of Recent Faults – IRC Insulation






# Obvious Risk of further IRC insulation faults



IRC Insulation known at risk locations	Pole 1	Pole 2
Onshore	4	5
Offshore	6	4

# No Issues with HV Elements of Cable



NO.	DESCRIPTION	THICKNESS	DIAMETER
18	INTEGRATED FO ELEMENT		
17	OUTER SERVING	4	Approx. 116
16	41 STEEL ARMOURING	7.5 x 2.5	108.1
15	BEDDING		103.1
14	IRC INSULATION	5.5	102.6
13	BEDDING		90.8
12	34 2. LAYER OF COPPER WIRE RET. COND.	7.5 x 2.4	90.1
11	BEDDING		85.3
10	32 1. LAYER OF COPPER WIRE RET. COND.	7.5 x 2.4	85.1
9	BEDDING		80.3
8	REINFORCEMENT	2 x 0.2	79.8
7	BEDDING		79.0
6	PLASTIC SHEATH (Slightly eccentric)	3.5 / 5.8	78.5
5	LEAD SHEATH	3.5	69.2
4	INSULATION SCREEN		
3	INSULATION, IMPREGNATED PAPER TAPES	11.5	60.5
2	CONDUCTOR SCREEN		
1	CONDUCTOR, COPPER		36.8

PDS.	QTY.	DESCRIPTION	NOM. THICKN. mm	NOM. DIAM. mm
05	111201	AS BUILT	HS	HS
ISSUE	DATE	REASON FOR ISSUE	DRAWN BY	PREPARED
SCALE	NTS	FRAME : A3	PROJECTION	NEXANS NORWAY AS
CLIENT:	MOYLE INTERCONNECTOR LTD NORTHERN IRELAND - SCOTLAND MOYLE INTERCONNECTOR		DRAWING TITLE: NOZFA-L 250 / 2 kV 1x1000/1150 mm <sup>2</sup> Cu	
CONTRACT NO.:	DOCUMENT CATEGORY:		NEXANS DRAWING NO.:	SHEET
			132976	5







# Replace LV Conductors – What a programme might look like

Major uncertainties on consents, factory availability and co-incidence with summer lay season - these will crystallise as plan progresses


Objective is to complete asap and run activities in parallel where possible

	2013	2014	2015	2016	2017
Specification					
Environmental definition					
Procurement					
Consenting		 			
Production (availability)			 		
Installation				 	
Commissioning					

# Reconfiguration Options




# Precise Location of Existing Fault







# Results of Autumn 2012 campaign



# Distributed Temperature Sensing (DTS)




# Hotspot when current injected



7550.562 7633.915 7782.324 7875.842 8001.888



# April 2013 offshore campaign on hotspot





# Summary

- Moyle's base case remains continued operation as single monopole using the integral HV & LV in the south cable
- The reliability of the single monopole is bolstered by recent successful testing of a "fallback" to run 250MW in the integral HV's – can be configured in 12hours
- There is a low level of confidence in LV part of cable system but there are no reasons to doubt the integrity of the HV elements of the cables
- The longer term strategy to return to full technical capacity at previous high levels of reliability is to replace the two LV conductors by laying two new LV cables
- This project has potentially a 4/5 year delivery with early uncertainties being considered as factory availability and consenting
- The feasibility of an interim option to run as a 500MW bi-pole using one or both of the [unreliable] IRC's at a much lower electrical loading is being reviewed
- Precisely pinpointing the current fault might enable a lower risk, lower cost repair to be engineered and considered